




- Notes
1. All dimensions in mm, unless otherwise stated.
 2. Scaling from drawing if printed incorrectly may lead to errors.
 3. All information outside red line boundary shown for contextual purpose only.
 4. All hatch patterns are indicative only unless stated otherwise.
 5. This drawing is to be read in conjunction with the following R.B.L.A landscape architecture documentation:
0009-RBL-XX-00-DR-L-0001
0009-RBL-XX-00-DR-L-0003
0009-RBL-XX-00-DR-L-0004
0009-RBL-XX-00-DR-L-0005
& all relevant documentation from the design team
 6. Levels information on this drawing illustrates the design intent. The contractor is to check and verify all levels and dimensions against site survey information.
 7. Any discrepancies in the design information are to be brought to the attention of R.B.L.A landscape architecture, in writing, prior to commencement of construction works.
 8. All proprietary products shall be installed in strict accordance with manufacturers written instructions.
 9. Refer to other consultants' drawings and specifications for the following design information:
 - Foundation details
 - Base course and/or sub bases design & specification
 - Waterproofing of any element
 - Levels & Drainage design and infrastructure
 - Lighting and ducting
 - Existing & proposed utilities
 10. Plant quantities are to suit site areas in accordance with scheduled plant densities.
 11. Any proposed plant substitution shall be agreed with the landscape architect prior to ordering.

- Key
- Planning application boundary
 - Paving type 1
400x300x30mm porcelain pavers
Colour: Neutral
Stretcherbond
build up to engineers specification
 - Composite decking
Composite decking with anti slip grip strips
Colour: Black/Grey
build up as per manufacturers recommendation
 - Gravel margin
granite aggregate chippings
aggregate size 6-9mm
 - Raised metal planters
600mm upstand powdercoated steel planters
RAL tbc
 - Timber benches
hardwood timber slat benches incorporated into raised planters
 - Proposed multistem trees
1-1.5m height multistem trees
refer to planting plan for species specification
 - Proposed specimen shrubs
80-100cm individual shrubs
Container grown
refer to planting plan for species specification
 - Proposed herbaceous planting
2L container grown plants
refer to planting plan for species specification
 - Proposed picnic bench
timber table and bench with
powder-coated steel supports
 - B Proposed Bee Pillar



05.08.26	Information Issue	P01
Date	Description of revision	Revision

R . B . L . A

www.rblandscape.co.uk
rosebarton@rblandscape.uk

Project
TY CAMBRIA
RB26-0009

Client
RHOMCO CONSULTING

Document title
LANDSCAPE GENERAL ARRANGEMENT
- 7th FLOOR

Paper size
A1

Status
FOR INFORMATION

Drawing number
0009-RBL-XX-00-DR-L-0003

Scale
1:50

Revision
S2

Revision
P01