



EXTERNAL PLANT







Water / Plant


Amenity

Amenity

- Notes
1. All dimensions in mm, unless otherwise stated.
 2. Scaling from drawing if printed incorrectly may lead to errors.
 3. All information outside red line boundary shown for contextual purpose only.
 4. All hatch patterns are indicative only unless stated otherwise.
 5. This drawing is to be read in conjunction with the following R.B.L.A landscape architecture documentation:
RBL-XX-00-DR-L-0001-General Arrangement Plan-Ground Floor
& all relevant documentation from the design team
 6. Levels information on this drawing illustrates the design intent. The contractor is to check and verify all levels and dimensions against site survey information.
 7. Any discrepancies in the design information are to be brought to the attention of R.B.L.A landscape architecture, in writing, prior to commencement of construction works.
 8. All proprietary products shall be installed in strict accordance with manufacturers written instructions.
 9. Refer to other consultants' drawings and specifications for the following design information:
 - Foundation details
 - Base course and/or sub bases design & specification
 - Waterproofing of any element
 - Levels & Drainage design and infrastructure
 - Lighting and ducting
 - Existing & proposed utilities
 10. Plant quantities are to suit site areas in accordance with scheduled plant densities.
 11. Any proposed plant substitution shall be agreed with the landscape architect prior to ordering.

Key

-  Planning application boundary
-  Paving type 1
400x300x30mm porcelain pavers
Colour: Neutral
Stretcherbond
build up to engineers specification
-  Gravel margin
granite aggregate chippings
aggregate size 6-9mm
-  Raised metal planters
600mm upstand powdercoated steel planters
RAL tbc
-  Timber benches
hardwood timber slat benches incorporated
into raised planters
-  Proposed multistem trees
1-1.5m multistem trees
Container grown
-  Proposed specimen shrubs
80-100cm individual shrubs
Container grown
-  Proposed herbaceous planting
2L container grown plants
7-9m2 density



Date	Description of revision	P01	Revision
05.08.26	Information Issue		

R . B . L . A

www.rblandscape.co.uk
rosebarton@rblandscape.uk

Project
TY CAMBRIA
RB26-0009

Client
RHOMCO CONSULTING

Document title
LANDSCAPE GENERAL ARRANGEMENT
- 23RD FLOOR

Paper size
A1

Status
FOR INFORMATION

Drawing number
0009-RBL-XX-00-DR-L-0002

Scale
1:50

S2

Revision
P01